

TREES & VEGETATION

- 30. THE CONTRACTOR SHALL VERIFY WHICH TREES ARE TO BE SAVED AND PROTECTED PRIOR TO COMMENCING CONSTRUCTION. DURABLE FENCE PROTECTION BARRIERS SHALL BE INSTALLED AROUND ALL TREES TO BE SAVED WITH FENCE PLACEMENT A MINIMUM OF 10 FEET FROM TREE CANOPY OR THE DRIP LINE, WHICHEVER IS GREATER.
- 31. THE CONTRACTOR SHALL NOT DISTURB AREAS AROUND EXISTING TREES TO BE SAVED.
- 32. THE CONTRACTOR SHALL PROTECT EXISTING GRASS, LANDSCAPING AND TREES NOT IN DIRECT CONFLICT WITH PROPOSED IMPROVEMENTS DURING CONSTRUCTION. GRASSED AREAS DAMAGED DURING CONSTRUCTION SHALL BE RESTORED BY THE CONTRACTOR WITH TOPSOIL AND SODDED.
- 33. THE CONTRACTOR SHALL REMOVE ALL VEGETATION, TREES, STUMPS, GRASSES, ORGANIC SOIL, DEBRIS, AND DELETERIOUS MATERIALS IN CONFLICT WITH IMPROVEMENTS.
- 34. AFTER THE CONTRACTOR HAS REMOVED MATERIALS AS DESCRIBED ABOVE, HE SHALL STRIP SUITABLE TOPSOIL AND STOCKPILE FOR LANDSCAPING USE.
- 35. THE CONTRACTOR SHALL EXERCISE EXTRA CARE TO AVOID DAMAGE TO TREES AND ORNAMENTAL SHRUBS PLANTED AND MAINTAINED BY PROPERTY OWNERS IN THE TERRACES FRONTING THEIR PROPERTY.
- 36. CONTRACTOR SHALL COMPENSATE OWNER FOR DAMAGE TO TREES NOT SHOWN TO BE REMOVED IN PLANS.
- 37. OAK TREES DAMAGED DURING CONSTRUCTION SHALL BE SEALED WITHIN SIX HOURS OF DAMAGE TO PREVENT INFECTION BY OAK WILT.

NPDES

- 38. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PREPARATION AND IMPLEMENTATION OF THE STORMWATER POLLUTION PREVENTION PLAN (SWPPP), INCLUDING COMPLYING WITH ALL APPLICABLE REGULATIONS RELATED TO NPDES & TPDES, AND SUBMITTING REQUIRED NOTIFICATION OF INTENT AND TERMINATION. THIS IS TO BE PAID FOR UNDER "STORM WATER POLLUTION PREVENTION PLAN" ITEM.
- 39. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE SITE CONDITIONS DURING CONSTRUCTION AND UNTIL THE PROJECT IS ACCEPTED. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING THE STORMWATER POLLUTION PREVENTION PLAN, UNDERSTAND THE REQUIREMENTS FOR THE PLAN, AND SHALL BE RESPONSIBLE FOR IMPLEMENTING THE PLAN. THIS IS TO BE INCLUDED UNDER SECTION 01410 "STORM WATER POLLUTION PREVENTION PLAN". ALL FINES IMPOSED FOR NOT IMPLEMENTING OR MAINTAINING SWPPP MEASURES SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.

SITE RESTORATION:

- 40. RESTORATION OF PROJECT AREA AFFECTED BY CONSTRUCTION ACTIVITIES IN PUBLIC AND PRIVATE PROPERTY, INCLUDING RIGHT-OF-WAYS AND EASEMENTS (TOPSOIL AND HYDROMULCH), PAVEMENT, DRIVEWAYS, DRAINAGE STRUCTURES, FENCES, LAWNS (TOPSOIL AND BLOCK SODDING), AND LANDSCAPING WILL BE COVERED BY SPECIFICATION AND BID ITEM "SITE RESTORATION" AND SPECIFICATION 01740 .
- 41. PAYMENT FOR RESTORATION OF PROJECT SITE DISTURBED BY UTILITY CONSTRUCTION OPERATIONS IS ON A LINEAR FOOT.
- 42. MEASUREMENT WILL BE AS PROVIDED FOR CORRESPONDING UTILITY IN EACH SPECIFICATION SECTION. NO SEPARATE PAYMENT MADE FOR BRANCH PIPE, VALVES, SERVICES, YARD PIPING AND OTHER ASSOCIATED WORK FOR UTILITIES. MEASUREMENT FOR RESTORATION WITH MULTIPLE UTILITIES WITHIN THE SAME RIGHT-OF-WAY WILL BE ON A LINEAR FOOT BASIS FOR ONLY ONE UTILITY.
- 43. PAYMENT INCLUDES REQUIRED SITE RESTORATION WITHIN THE RIGHT-OF-WAY OR EASEMENT REGARDLESS OF SIZE OR TYPE OF PIPE, METHOD OF CONSTRUCTION, PAVED OR UNPAVED AREAS OR THICKNESS AND WIDTH OF PAVEMENT.
- 44. NO SEPARATE PAYMENT MADE FOR SITE RESTORATION FOR SERVICE CONNECTIONS OR YARD PIPING UNDER THIS SECTION. INCLUDE COST IN APPROPRIATE ITEM.
- 45. ALL DISTURBED AREAS TO BE RE-VEGETATED TO 85% OF APPROVED GRASSES ACCORDING TO THE UDC PRIOR TO THE ACCEPTANCE OF PERMIT CLOSEOUT.
- 46. ROUGH GRADING, INCLUDING TREE REMOVAL MUST BE DONE ON ALL LOTS PRIOR TO SUBDIVISION PRELIMINARY ACCEPTANCE.



**NPDES**

XX

ENGINEERING AND PUBLIC WORKS

SCALE: N.T.S.

DATE: 7/1/19

DSGN BY: ENG.

DRAWN BY: BCP

SHEET NO.: 3 of 6