



**NOTES:**

1. CONTRACTORS SHOULD USE HTH FOR DISINFECTION OF WATER LINES (NOT CHLORINE INJECTION) UNLESS APPROVED OTHERWISE PRIOR TO ISSUANCE OF PERMIT.
2. NEW WATERLINES SHALL BE TIED INTO EXISTING WATER SYSTEM UNDER THE SUPERVISION OF CITY PERSONNEL NO LATER THAN 14 DAYS AFTER PASSING BACTERIOLOGICAL TESTS.
3. ALL SERVICES ARE TYPE "K" COPPER.
4. METER BOXES WILL BE ACCOMPANIED BY AN "X" ETCHED INTO CURB FACE PAINTED BLUE.

C:\Users\JUS155\City of Schertz\Engineering Department - Documents\Standards and Details\Standard Details\2018\WATER\STANDARD WATER DETAILS 02232018.dwg



STANDARD DETAIL 02512  
 WATER TAP AND SERVICE  
 TECHNICAL SPECIFICATION SECTION 02512

ENGINEERING AND PUBLIC WORKS

SCALE: N.T.S.  
 DSGN. BY: ENG. DRAWN BY: JRS

DATE: 2/09/2021  
 SHEET NO: 1 of 1