



GENERAL NOTES

1. THE CONTRACTOR SHALL PLACE FLOWABLE FILL A MINIMUM OF 1-FT. AROUND WALLS, FROM THE BOTTOM OF BASE UP TO THE BOTTOM OF CONCRETE COLLAR. PER SPEC. 02081 AND 02082.
2. TOP SECTION SHALL BE FLAT TOP WITH CONCENTRIC HOLE.
3. WALL REINFORCEMENT SHALL BE DESIGNED BY ENGINEER FOR CAST-IN-PLACE MANHOLES.
4. PROVIDE WATERTIGHT SEAL BETWEEN PRECAST CONCRETE ADJUSTMENT RINGS AND MANHOLE COVER FRAME, AROUND MANHOLE, HDPE RINGS, AND MANHOLE RISER JOINTS PER SPEC 02081, 02082, AND 02083 (GATORWRAP OR APPROVED EQUAL).
5. INTERIOR MANHOLE WALLS SHALL BE COATED WITH AN APPROVED LINER PER SPEC 02081 AND 02082 .